


**NOTES:**

1. LOCATE AT ENDS OF MAIN, ALL HORIZONTAL BENDS AND AT 300 FT. MAX SPACING, OR AS REQUIRED BY DISTRICT
2. ON HDPE PIPE, PROVIDE 12 GAUGE COATED COPPER WIRE BETWEEN LOCATION BOXES. WRAP ALONG PIPE AND UP COPPER PIPE AT EACH END.
3. BACKFILL MATERIAL AND COMPACTION SHALL BE IN CONFORMANCE WITH SILVER LAKE WATER AND SEWER DISTRICT STANDARDS AS SHOWN ON DETAIL G6.

 <p><b>Silver Lake Water &amp; Sewer District</b></p>	
<p><b>LOCATE BOX</b></p>	
<p>DATE: 11-2022</p>	<p>DWG: G11</p>